## Status of the Advanced Virgo detector

F. Piergiovanni

on behalf of The Virgo Collaboration



GWPAW, Osaka, 06/17/2015



### Talk outline

- The Advanced Virgo challenges
- Where we stand and what we are going to do
- Construction and integration highlights
- Perspectives and conclusions



## The Advanced Virgo project

Advanced Virgo is a major upgrade of the Virgo ground based gravitational wave interferometric detector





The project involves: 5 countries, 20 labs and ~200 authors. APC Paris ARTEMIS Nice EGO Cascina **INFN** Firenze-Urbino INFN Genova INFN Napoli **INFN** Perugia INFN Pisa INFN Roma La Sapienza **INFN** Roma Tor Vergata INFN Trento-Padova LAL Orsay - ESPCI Paris LAPP Annecy LKB Paris LMA Lyon NIKHEF Amsterdam POLGRAW(Poland) RADBOUD Uni. Nijmegen RMKI Budapest



## The short history



• 2<sup>nd</sup> generation of interferometric GW detectors :



#### aLIGO, AdVirgo, GEOHF, KAGRA, LIGO India



## The sensitivity curve





## The main changes: how to gain a factor 10

#### The low and medium frequency range

- Lowering the thermal noise of suspensions and mirrors:
  - ✓ Doubling the mirror weight (42kg)
  - $\checkmark$  Suspending the mirrors with fused silica fibres
  - $\checkmark$  Enlarging the beam size on the test masses
  - $\checkmark$  Mirror coatings engineered for low dissipations





• Lowering the residual gas noise:

✓ installing cryotraps



- •Limiting the environmental noise:
  - ✓ Photodiodes under vacuum on suspended benches
  - $\checkmark$  Baffles to shield tubes, mirrors, vacuum chambers preventing scattered light diffusion









## The main changes: how to gain a factor 10





## A step by step approach

#### The mail goal is to join aLIGO in 2016 observational runs

- Reach the early configuration sensitivity :
- no signal recycling
- no high power laser ( up to 25W )

#### Reducing :

- locking complexity (optics configuration similar to Virgo+)
- the thermal effects and the compensation system requirements

Further steps towards the full sensitivity will be planned with the partners













- A 60W laser system (Virgo+) is already installed and in operation
  - The power stabilization works at 23W and all the noise spectrum is well understood
- The high power laser amplifier is under tests:
  - ✓ the AdVirgo requirements are satisfied in terms of lifetime stability and intensity noise
  - ✓ Full scale integration test are ongoing.







#### SIB1

#### Installed & integrated in tower





#### The EIB in the Laser lab



#### SIB2 completed

#### Minitower installed

#### Integration is ongoing





#### The IMC end mirror in tower







- The Input Mode Cleaner commissioning has started one year ago
- Duty cycle continuously improving (99% during weekends)
- Tested up to 31W of input power

• Reference cavity locked since November 2014

- The noise has been reasonably well understood
- The noise hunting is ongoing





#### Mirrors





## Mirrors

• All the AdVirgo large mirrors have been completed on schedule

✓ The mirror figures are better than the specifications

Risk reduction for aberration and scattered light

Mirror "maps" are used in simulations to predict the interferometer behavior





| Incidence 0°  | Advanced VIRGO<br>Requirements<br>removed) |  | LMA<br>Measurements<br>£2150 mm               |
|---|--|--|---|
| Radius of Curvature (m)<br>Surface 1                      | 1425 +/- 10 m<br>⊘ 150 mm                  |  | 1424.56 m<br>⊘150 mm                          |
| Astigmatism amplitude<br>(Zernike term)°                  | < 5nm<br>Ø 150 mm                          |  | 0.52 nm<br>⊘150 mm                            |
| Transmitted wavefront<br>Incidence 0°<br>(before coating) | x  |  | 0.77 nm RMS<br>Ø150 mm<br>(Curvature removed) |
| Average Scattering<br>(45° incidence)<br>Surface 1        | < 10 ppm<br>Ø 150 mm                       |  | 3 ppm<br>∅ 150 mm                             |
| Absorption HR<br>Surface 1                                | < 0.5 ppm                                  | 0.22 +/- 0.06 ppm<br>⊘150 mm                                       |   |
| Transmission<br>at 1064 nm<br>1° incidence                | 1.4 +/- 0.1%                               | 1.375 % +/- 0.007%<br>⊘150 mm                                      |   |
| Transmission<br>at 532 nm<br>0* incidence                 | 0.5% < T< 2%                               | 1.01%<br>(witness sample,<br>spectrophotometric<br>measurement)    |   |
| Reflectivity AR Surface 2<br>at 1064 nm<br>3° incidence   | <100 ppm                                   | 58 +/- 9 ppm<br>∅ 150mm  |   |
| Reflectivity AR Surface 2<br>at 800 nm<br>0° incidence    | <1%  | # 0.1%<br>(witness sample,<br>spectrophotometric<br>measurement)   |   |
| Reflectivity AR Surface 2<br>at 532 nm<br>0° incidence    | 2%   | # 0.2%<br>(witness sample,<br>spectrophotometric16<br>measurement) |   |



## Mirrors



- The "ears" have been silicate bonded to the mirror flats on 3 over 4 test masses
- Each bonding strength is tested





The beam splitter has been the first large mirror integrated in tower A large beam needs a large BS: 550 mm diameter







## Suspensions





#### Suspensions





#### Suspensions



The electronics has been redesigned from scratch: integration foreseen in fall 2015

integrated







#### Thermal compensation

#### The actuators



- CO2 laser has been characterized
- CO2 laser benches almost complete
- Acoustic enclosure already on site

• The ring heaters production and integration will follow the payloads integration planning

•The first installed RH follows the prototypes behavior







#### Thermal compensation

#### The sensors

- The Hartmann wavefront sensor:
  - $\checkmark$  The design has been finalized
  - $\checkmark$  The installation is in progress
  - ✓ Many tests are underway on a dedicated test facility



- The phase camera:
  - ✓ Installation and tests on the devices are underway
  - $\checkmark$  Integration with the compensation system is in progress







## Signal detection

- The detection system main optical bench has been installed
- Integration is foreseen soon





- A new Output Mode Cleaner has been realized:
- Developed for DC detection
- Two monolithic cavities in series
- Filtering high order modes and optical field



#### Signal detection

Mini-towers:



• Five new minitowers have been produced to suspend in vacuum photodiodes benches

•Pre-commissioning with dummy mass in progress











#### Vacuum system

#### Cryotraps & enlarged links

- Cooling-down test achieved for the two cryotraps placed at the end towers
- The main vessels are installed at the inputs and the integration is quite complete
- two smaller cryostats are being installed at the short tower







enlarged links installation is almost completed



#### Commissioning

- Reaching the design sensitivity is a long term effort
- In spite of the increasing complexity the expected AdVirgo commissioning duration is much shorter than for Virgo



- A lot of experience gained
- Many instrumental weaknesses solved (mirror quality, new payload design, thermal compensation...)
- Environmental isolation improved (stray light mitigation, acoustic enclosures, ...)
- The impressive experience of the extremely fast aLIGO commissioning



#### Commissioning

General co

Calibration

Arm hudee

relative calibration IT asymetric Michelson

sure arm cavity

The plan in a sketch:

- The commissioning is already started on light injection system and IMC
- Many tests have been anticipated to save time also on other sub-systems
- The step by step procedure foresees:



Jul 15 Aug 15 Sep 15 Oct 15 Nov 15 Dec 15 Jan 16 21 28 5 12 19 26 2 9 16 23 30 6 13 20 27 4 11 18 25 1 8 15 22 29 6 13 20 27 3 10 17 24

-

3/4/2015 211.33 d 11/3/2015 10 days

11/3/2015 2 wks

11/10/2015 1 wk

11/10/2015 5 days



#### Conclusion

- Advanced Virgo is currently in a crucial phase of installation
- A lot of parallel activities are ongoing requiring a big and constant organization effort
- The schedule is very tight and all the arising issues have to be promptly faced coordinating the works of all the groups
- All the groups are fully committed to end the installation/integration phase within 2015 to achieve the first lock in the first months of 2016
- The main target is to join LIGO in observational run during 2016
- The steps towards the transition to the full configuration will be decided with the partners

